

PROPOSAL REQUEST

PROJECT:
Sturgis Brown High School Office Remodel
Sturgis, South Dakota

OWNER:
Meade School District #41-6
1230 Douglas Street
Sturgis, SD 57785

CONTRACTOR:
Scull Construction
803 Industrial Avenue
Rapid City, SD 55702

PROPOSAL REQUEST NO.: #1
DATE OF ISSUANCE: May 3, 2016
CONTRACT FOR: Prime
CONTRACT DATED: February 24, 2016
ARCHITECT'S PROJECT NO.: 2642

ARCHITECT:
Architecture Incorporated
815 St. Joseph Street
Suite 203
Rapid City, SD 57701

Please submit an itemized proposal for changes in the Contract Sum and Contract Time for proposed modifications to the Contract Documents described herein. Submit proposal or notify the Architect in writing of the date on which you anticipate submitting your proposal.

THIS IS NOT A CHANGE ORDER, CONSTRUCTION CHANGE DIRECTIVE, OR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED IN THE PROPOSED MODIFICATIONS.

Description: VCT Flooring Demolition & Carpet Change

1. It was discovered that the existing floor tile and adhesive scheduled for demolition contained asbestos. The owner will remove the required tiles to allow for installation of the new plumbing below grade, but the remainder of the flooring will remain in place. Carpet tile will be installed directly over the existing VCT.
 - a. Please provide a credit to the owner to delete the removal of the existing VCT in the four existing classrooms as called out on sheet 4.1
 - b. Install new VCT over patched concrete floor in rooms 175,176,177,178, 179. VCT for those areas will be provided by the owner. Installation of new VCT in Corridor 162 to remain as shown on sheet 4.4 Finish Plan.
 2. Change CPT-1 Tandus Accentuate (strike-off reference for this color is 1018356-001; Sturgis Brown High School) from 6' wide roll good to 2'x2' carpet tiles.
-

Requested by: Jordan Burbach, Architecture Incorporated
